



REMOVE AND REPLACE EXISTING STRUCTURE.

REMOVE/ABANDON EXIST. 8" PVC AS NECESSARY. SMOKE TEST FOR REMAINING CONNECTIONS, PLUG AND BACKFILL EXISTING PIPE IF ABANDONED.

MAINTAIN CONTINUOUS SERVICE IN 30" X 22" BRICK LINE.

REPLACE EXISTING 9"x9" BRICK BETWEEN EXISTING STRUCTURES 224 AND 158 WITH 26LF OF 18" RCP
 $INV_{IN} = .82$
 $INV_{OUT} = .30$

REMOVE AND REPLACE EXISTING STRUCTURE. CONNECT EXIST. UPSTREAM 42" CONC. PIPE TO PROPOSED STRUCTURE.

REMOVE/ABANDON EXISTING PIPE AND STRUCTURES BETWEEN PLUG AND SD-61 AS NECESSARY. SMOKE TEST FOR REMAINING CONNECTIONS. PLUG AND BACKFILL EXISTING PIPE IF ABANDONED.

REFERENCE C-009



CIVIL
 F-22 INFRASTRUCTURE AND STORM SEWER UPGRADES
 SK005

NOTE:
 AS PER RECORDS, 8" WATER