Permanent Tidal Marsh Impact 214.3 S.F.

Edge of Tidal Marsh

Route 33

Permanent Tidal Marsh Impacts 16,432.5 S.F.

Temporary Tidal Marsh Impacts 8.8 S.F.

Proposed Temporary Construction Trestle

Proposed Right of Way

MATCH LINE STA. 112+00 PLATE 2

SCALE 0 50' 100'

LEGEND

TIDAL MARSH

OPEN WATER

WETLAND BOUNDARY

TIDAL WATER BOUNDARY

LIMITS OF CUT

LIMITS OF FILL

TEMPORARY EASEMENT

PERMANENT EASEMENT

Temporary Trestle Impacts Based On 0.004 Sq. Ft. Of Piles Per Sq. Ft. Of Deck (Main Trestle) And 0.007 Sq. Ft. of Piles Per Sq. Ft. Of Deck (Finger Piers)

IMPACT AREA

PERM. TIDAL MARSH IMPACTS:	16,646.8 S.F.
TEMP. TIDAL MARSH IMPACTS:	8.8 S.F.
PERM. OPEN WATER IMPACTS:	0.00 Ac.
TEMP. OPEN WATER IMPACTS:	0.00 Ac.

ROUTE 33 BRIDGE REPLACEMENT

VDOT PROJECT NO. 0033-063-103, PE-102

PLAN VIEW

SCALE: 1"=50'-0"

DATE: JAN 20, 2003

PLATE 1 OF 22

...\CADD\permit_plates\Plate01.dgn 03/17/2003 09:16:59 AM