



SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

## Changes in Section SF 30

## Amendment 5

## Technical Information:

The following information is incorporated into the technical specifications and drawings:

1. Sheet A125D, Finish Schedule - Demolition, Finish Schedule  
Notes - Demolition, note 5 states "remove existing flooring, subfloor and wood joists." There are no structural details of the existing building to define the extent of this scope of structural removal work on the first and second floor framing. How far back are the joists to be removed, how does joist removal affect the existing adjacent subfloor and wood flooring.

Removal is confined to this room on both the first and second floor. The joists were lowered and concrete poured during a previous bathroom renovation.

2. See note 1 above: There are no details dealing with the replacement of this flooring that was removed. Please provide more details.

In all bathrooms in all types of buildings (GOQ's and EQ's) new joists shall be provided in the areas where the flooring, concrete and joists were removed. In the Enlisted Quarters, Finish Schedule Note - New Work 7 covers the replacement of the flooring in this area.

3. See note 1 above: under existing ceiling finish the note is PLAS/GWB. General note C states that "in many rooms a second GWB ceiling has been installed on furring". What is the quantity of this second layer of GWB in each unit?

For bid purposes assume the entire first floor and the second floor hallway and bathroom. There is no way to verify this quantity until work begins in each unit.

4. Sheet C-102D, TYPICAL NEW CONSTRUCTION AND NEW UNDERGROUND UTILITIES has a note "see note 2 sheet C-102D" and points to the abandoned downspout boots. However, Note 2 on C-102D refers to sidewalk concrete thicknesses. What is the correct note reference and scope of work that these arrows are pointing to?

Note should read "SEE NOTE 2 SHEET C-103D"

5. Sheet C-103D, Notes 2 in the lower left corner of the page, conflicts with note 21 on A-102D (typical). Please clarify.

Work at existing downspout boots will be as described in note 21 on A-102D