Impacts due to APM Terminal Dredging and the Berthing of Ships at both the CIEE and APM sites

by

Mac Sisson, Harry Wang, and Yaping Wang

Virginia Institute of Marine Science /
School of Marine Science
College of William and Mary



Background

- APM Terminal dredging was not known at the time of original study
- VPA requested VIMS to analyze the longterm, far-field hydrodynamic impacts resulting from this dredging
- In addition, berthing of ships at both the CIEE and APM sites was evaluated




- Review prior CIEE study and results
- Assess impacts of dredging at APM site
- Assess impacts of ship berthing at both sites
- Compare these impacts to those of the original expansion options
- Flushing evaluation (simulated dye release)




Hampton Roads

Location of Study Area




VIMS HEM-3D Model

- Predicts real-time tide, velocity, salinity, and sedimentation potential
- Uses a variable grid dimension
- Incorporates man-made structures
- Performs with stability even under extreme conditions (e.g., variable discharge, high wind)




Global Analysis

- Determine average differences of test case from base case cell-bycell
- Plot these differences spatially
- Sort these differences on an areal basis
- Compare 95th Percentiles
 values exceeded by
 - only 5% of the total area





Base Case


- Define "Base Case" to be the existing condition (e.g., I-64 and I-664) but also to include future VDOT Third Crossing
- Quantitatively assess impacts of all test cases by comparing each scenario run to the Base Case
- For consistency, the Base Case of the current study was exactly that of the original study




Expansion Options Originally Modeled










Global Change - 95th Percentile

(5% of area contains change greater than value listed)

Change in:	East 50'channel	West 50'channel	North 50'channel	N-East 50'channel
Surface Elev.	0.14 cm			
Surface Current	2.4 cm/s			
Bottom Current	1.6 cm/s			
Surface Salinity	0.00 ppt			
Bottom Salinity	0.00 ppt			
Sedimentation Potential	0.08%			

- Review of prior CIEE study and results
- Assessment of impacts of dredging at APM site
- Assessment of impacts of ship berthing at both sites
- Comparison of these impacts relative to those of the original expansion options
- Flushing evaluation (simulated dye release)





Setup of Model Run APM Terminal Site Dredging

• Site specifications:


- dredging depth: 52 feet MLLW (16.2 m NGVD)
- area: 189 acres (0.765 km^2)
- volume: 10.3 million yds³ (7.875 million m³)


• Model consistency check:

- dredging depth: 16.2 m NGVD (as specified)
- area: 0.747 km^2 (within 2.4%)
- volume: 7.837 million m³ (within 0.5%)


Spatial Plots (APM dredging impact)


- Surface Elevation RMS difference
- Salinity Avg. Difference (surface & bottom)
- Velocity Magnitude RMS (surf. & bottom)
- Residual Vel. Mag. Avg. Diff. (surf & bot)
- Sedimentation Potential Difference








Elizabeth River Salinity – Natural Variability
























- Review of prior CIEE study and results
- Assessment of impacts of dredging at APM site
- Assessment of impacts of ship berthing at both sites
- Comparison of these impacts relative to those of the original expansion options
- Flushing evaluation (simulated dye release)





























Global Change - 95th Percentile

(5% of area contains change greater than value listed)

	CIEE	CIEE +	CIEE +APM	CIEE +APM
Change in:	only	APM dredging	dredging + triangular ships	dredging + square ships
Surface Elev.	0.14 cm	0.13 cm	0.13 cm	0.14 cm
Surface Current	2.4 cm/s	2.4 cm/s	2.5 cm/s	2.6 cm/s
Bottom Current	1.6 cm/s	1.7 cm/s	2.1 cm/s	2.5 cm/s
Surface Salinity	0.00 ppt	0.10 ppt	0.15 ppt	0.19 ppt
Bottom Salinity	0.00 ppt	0.06 ppt	0.10 ppt	0.15 ppt
Sedimentation	0.08%	0.08%	0.09%	0.10%
Potential				

- Review of prior CIEE study and results
- Assessment of impacts of dredging at APM site
- Assessment of impacts of ship berthing at both sites
- Comparison of these impacts relative to those of the original expansion options
- Flushing evaluation (simulated dye release)



Global Change - 95th Percentile

(5% of area contains change greater than value listed)

Single Variable - 50' Channel Cases

Change in:	Eastward	Eastward + dredging + ships	Westward	Northward	Northeastward
Surface Elevation	0.14 cm	0.14 cm	0.34 cm	1.00 cm	1.04 cm
Surface Current	2.4 cm/s	2.6 cm/s	5.3 cm/s	12.3 cm/s	11.7 cm/s
Bottom Current	1.6 cm/s	2.5 cm/s	3.3 cm/s	7.8 cm/s	6.6 cm/s
Surface Salinity	0.00 ppt	0.19 ppt	0.12 ppt	0.71 ppt	0.23 ppt
Bottom Salinity	0.00 ppt	0.15 ppt	0.35 ppt	1.00 ppt	0.23 ppt
Sedimentation Potential	0.08 %	0.10 %	2.8 %	8.9 %	6.3 %

Global Change – 95th Percentile

(5% of area contains change greater than value listed)

Historical – High Discharge Event

Change in:	Eastward 50'	Eastward + Dredging + Ships	Eastward-Westward 50'
Surface Elevation	0.20 cm	0.20 cm	0.33 cm
Surface Current	5.5 cm/s	5.9 cm/s	6.7 cm/s
Bottom Current	2.7 cm/s	3.6 cm/s	3.7 cm/s
Surface Salinity	0.00 ppt	0.08 ppt	0.02 ppt
Bottom Salinity	0.00 ppt	0.09 ppt	0.07 ppt
Sedimentation Potential	1.0 %	1.1 %	1.9 %

Global Change – 95th Percentile

(5% of area contains change greater than value listed)

Historical – Low Discharge Event

Change in:	Eastward 50'	Eastward + Dredging + Ships	Eastward-Westward 50'
Surface Elevation	0.14 cm	0.14 cm	0.33 cm
Surface Current	2.7 cm/s	3.0 cm/s	4.3 cm/s
Bottom Current	1.9 cm/s	2.7 cm/s	2.9 cm/s
Surface Salinity	0.00 ppt	0.12 ppt	0.04 ppt
Bottom Salinity	0.01 ppt	0.16 ppt	0.09 ppt
Sedimentation Potential	0.9 %	1.0 %	2.8 %

Global Change – 95th Percentile


(5% of area contains change greater than value listed)


Historical – High Wind Event


Change in:	Eastward 50'	Eastward + Dredging + Ships	Eastward-Westward 50'
Surface Elevation	0.21 cm	0.21 cm	0.46 cm
Surface Current	2.2 cm/s	2.8 cm/s	5.0 cm/s
Bottom Current	1.5 cm/s	2.4 cm/s	3.0 cm/s
Surface Salinity	0.00 ppt	0.09 ppt	0.00 ppt
Bottom Salinity	0.00 ppt	0.11 ppt	0.02 ppt
Sedimentation Potential	0.8 %	0.9 %	1.7 %

- Review of prior CIEE study and results
- Assessment of impacts of dredging at APM site
- Assessment of impacts of ship berthing at both sites
- Comparison of these impacts relative to those of the original expansion options
- Flushing evaluation (simulated dye release)









Conclusions

- With the APM terminal site located in a low energy region, dredging and ship berthing both have a relatively small impact.
- Both APM terminal dredging and the berthing of ships have minimal impact on either surface elevation or sedimentation potential.
- Berthing of ships at CIEE, if considered permanent, has a localized effect on the salinity distribution, and to a lesser extent, the velocity distribution.



Conclusions (con't.)

- Cumulative far-field impacts resulting from both dredging and ship berthing occurred on velocity and salinity distributions, but their magnitudes were less than those of the previously studied land expansions.
- The flushing of the Elizabeth River shows no detectable adverse response from the combined effects of the APM terminal dredging and ship berthing.

