

C.1.4.3.1 Essential Services

The following services are identified as essential during the performance of this contract IAW DFARS Clause 252.237-7023. Continued performance of these services without disruption is required during curtailment of operations. The Contractor is required to provide a written plan to the KO identifying how they will perform these services when notified of curtailment of operations by the KO. The written plan will be incorporated into the contract. Priority 1 Demand Maintenance Orders (DMOs)

Customer Services

Fire Suppression Systems

Snow Removal

Refrigeration, Ventilation and Air Conditioning

Electrical Distribution

Potable Water Distribution

Airfield Lighting

Gas Distribution

Emergency Generator Systems

Sanitary Wastewater Treatment

Uninterruptible Power Systems

Micro grid Operation and Maintenance

C.4.4 Cleanliness

The Contractor shall maintain GFF, equipment, vehicles, supplies, and material in a safe, organized, and clean condition including facilities, yards, compounds, parking areas, and ancillary work areas. The Contractor shall maintain all outdoor areas assigned to the Contractor for its use (including 50 feet around any Contractor-assigned facility) free of trash, debris, undesirable vegetation, and leaves. The Contractor shall also be responsible for the removal of snow and ice from walkways of Contractor-assigned facilities.

C.5.5.2.1.9 Granular product.

Sweep primary roads starting within 48 hours after last snowfall or when the roads are clear of snow and ice and complete within three working days during winter months, when a granular product is used for a de-icing.

C.5.5.3 Snow Removal and Ice Control.

Snow removal and ice control services are the plowing and removal of snow, and ice control of streets, sidewalks, and parking. A list of snow removal and ice control priorities areas is in section C.8, TE-FF. Historical snowfall data for Dugway Proving Ground is in section C.8, TE-FF-1. Sidewalks and parking lots are subject to the same snow depth guidelines as street snow removal.

C.5.5.3 Snow Removal and Ice Control.

Snow removal and ice control services are the plowing and removal of snow, and ice control of streets, sidewalks, and parking. A list of snow removal and ice control priorities areas is in section C.8, TE-FF. Historical snowfall data for Dugway Proving Ground is in section C.8, TE-FF-1. Sidewalks and parking lots are subject to the same snow depth guidelines as street snow removal.

C.5.5.3.7 Priority sequence of work.

Perform work in priority sequence identified by the snow response plan. Accomplish snow removal of sidewalks concurrently with roads as warranted.

C.5.5.3.16 Liquid de-icing material.

Apply liquid de-icing material pre-storm and as required during and post storm in any location required for de-icing. Remove snow as necessary in these locations prior to applying deicing material to increase its effectiveness. Determine the necessity for applying deicing material on streets and parking areas in order to maintain effective braking traction on traffic surfaces. Notify the Government in accordance with the notification procedures for plowing operations described in Section C.5.5.3.6 when de-icing material is being applied. Do not use deicing material that may hinder final denial barrier operation or corrode components of the system within 50 feet of the barriers.

C.5.5.3.17 End of snowstorm.

At end of snowstorm and after traffic flow has been restored, push back snow berms along roadsides so that melting snow will drain into drainage systems or adjacent grounds rather than onto traffic surfaces. Remove snow or snow berms that hinder vehicular or pedestrian access to buildings, fire hydrants or dumpsters, or restrict vehicular and pedestrian traffic; obstruct vision of traffic or hinder proper operation of traffic control devices; or hinder deliveries to Dining Facilities within eight hours.

C.5.5.3.18 Secondary Roads.

Perform snow removal and ice control on secondary roads and parking lots during normal work hours unless storm is classified as a major event requiring other response.